

31 Gov't Land Corner Ties

Muscatine County

DIETZGEN

78-4W

FIELD BOOK

Book 3

No. 403P

T78N-R4W

Wapsie Township

Check 10/1/39 add

31

ML

See Book #1 for Index

Final Check
E.I. 9-15-42.
all information
copied

* NIA


2
 S $\frac{1}{4}$ CORNER, Sec - 32 - T78N - R4W
 MONUMENT - PREVIOUSLY - SET
 BY - J. T. RYAN - WHOSES - NOTES
 SHOW - NO - O.R.G. EVIDENCE -
 FOUND - MON SET - IN - 8" CF -
 E/W - ROAD - IN - LINE - WITH - V
 FENCE - LINE.

117.8' W. OF MON. N $\frac{1}{4}$ COR. SEC - 5 - T78N - R4W
 60.3' S.V. OF X SPKS. IN 24" Maple
 47.8' W.S.W. of X SPKS. in 30" Maple
 279.3' E.N.E. of N.E. COR. of BAR
 56.5' N.E. of X SPKS. in 1st page.
 35.5' S.S.W. of X SPKS. in Cor Post. Face N.
 121.4' N.W. of X SPKS. in Cor Post. Face S.

MONUMENT - BURIED - 18" D.I.P

32

STAMPED -




W $\frac{1}{4}$ CORNER - Sec - 31 - T8N R-4-W
 MONUMENT - PREVIOUS SET -
 BY - J. F. RYAN - W. H. SSES - NOTES
 SHOW - NO - ORIG. EVIDENCE -
 FOUND. MON - SET - IN - ϕ OF
 NTS, ROAD - IN - LINE - WITH - E
 FENCE

Stone in ϕ of NTS Road Fence E.
 928.8' S.W. of S.W. Cor of H.L. Heather Res.
 58.5' S.W. of X SPKS in Power Pile
 33.7' W. of X SPKS in Cor Post. Fence E.
 35.8' N.E. of X SPKS in ϕ of phone pile
 602.4' S.E. of S.E. Cor of BARN
 287.3' N.W. of X SPKS in Power Pile
 33.6' E. of steel fence post
 67.2' R.O.W. in Road N. & S.

MONUMENT - BORED - 12" deep

31 - 32

STAMPED -



NE CORNER - Sec. 31 - T18N R. 4-W
 MONUMENT PREVIOUSLY SET
 BY J. J. RYAN - WHOSES NOTES
 SHOW - A - HUB - WAS - FOUND.
 MON. SET IN - $\frac{1}{2}$ OF N + S - ROAD
 IN - LINE - WITH - E. FENCE.


Stone in $\frac{1}{2}$ of N + S Road. Fence $\frac{1}{2}$
 907.6' S.E. of S.W. Cor of BRIDGE
 907.6' S.S.W. of S.E. Cor. of BRIDGE
 241.6' N.W. of X SPKS in Power Pole
 54.2' S.W. of X SPKS in Power Pole
 33.6' W. of X SPKS in Cor Post. Fence $\frac{1}{2}$
 307.5' N.E. of A. Stee. 2. Cor Post. Fence W.
 33.0' E. of R.O.W. Fence on W. Side of Rd.
 66.6' R.O.W. in Road N + S.

MONUMENT - BURIED - 12" Deep

30 29

31 32

STAMPED -



N 40° RNER-SEC-31-778N R 4-U
 MONUMENT-PRY 4514-3c-BY
 JET. MAY-WHOSAS-NOTES-SHOW
 NO-ORANGE-ICE-FOUND
 MON SET-ON-IV-S-DE-OF-N-S
 FENCES-IN-LINE-WITH-E
 FENCE.

Stone at intersection of N. 778 E. Pos.

0.5' W. of SPRING in Post Fence

800' N. of SPRING in E. fence post to S


100' S. of SPRING in fence post to N

No other L. S. AVAILABLE

MONUMENT SURFACE LEVEL

29

STAMPED - 32




6
 W $\frac{1}{4}$ CORNER Sec-29-T78N-R-4-W
 MON. PREVIOUSLY SET BY J.T. RYAN
 WHOSES NOTES SHOW A HUB
 WAS FOUND MON. SET IN E.O.F. NTS
 ROAD - IN LINE WITH W. FENCE.

117.6' S.W. of X SPKS in Cor Post. Force Fu.
 33.0' W. of R.O. W. fence - RUNNING N.S. E. Side R.
 33.5' E. of X SPKS in Cor Post. Fence West.
 194.5' S.W. of X SPKS in Power Pole.
 251.3' N.W. of X SPKS in Power Pole.
 103.2' N.E. of X SPKS in Gate Post. N. SIDE
 OF FIELD ENTRANCE.
 66.5' R.O. W. in ROAD NTS.

MONUMENT BURIED - 12" DEEP

30-29

STAMPED -




N¹/₄ CORNER - Sec - 29 - T78N - R4W
 MON. PREVIOUSLY SET BY JAT. N.Y.A.N.
 WHOSE NOTES SHOW A STONE
 WAS FOUND MON. SET IN E OF
 E & W ROAD AND IN LINE
 WITH NTS FENCE LINES.

33.1' 1. EX SPKS. in Cor. Post. Fence South
 32.9' S. of Steel Cor. Post. Fence North
 513.8' N.E. of N.E. Cor. of R.R. 2nd pk W^{2d} Res.
 123.7' S.W. of X SPKS. in telephone pole
 152.8' N.W. of X SPKS. in Power Pole.
 27.0' S.E. of X SPKS. in telephone pole.
 66.0' P.O. in Road E & W.

MONUMENT BURIED - 12" DEEP

20
 STAMPED - 29




NE CORNER - Sec - 30 - T4N - R-4-W
 MON. PREVIOUSLY SET BY AT AT
 RUAN - WHOSES NOTES - SHOW
 AN IRON PIN WAS FOUND MON
 SET IN E OF NTS - E + W - RDS.

- 470.5' E.S.E. of HANDRAIL of BRIDGE N Side
- 44.2' S.E. of Telephone pole. (X SPKS.)
- 42.7' SE. of X SPKS. in Cor Post Fence S.W.
- 45.6' S.W. of X SPKS. in Power Flasher Pole
- 47.1' S.W. of X SPKS. in Cor Post Fence N.E.
- 55.1' N.W. of X SPKS. in Cor Post Fence E.S.
- 45.2' N.W. of X SPKS. in Power Pole
- 44.7' N.E. of X SPKS. in Cor Post Fence S.W.
- 83.2' N.W. of X SPKS. in 18" Pine.
- 96.3' N.E. of X SPKS. in 28" Maple.

MONUMENT - BURIED - 12" DEEP

19 20

STAMPED - 30 29



NE CORNER - Sec - 19 - T8N - R - 4 - W.
 MON. PREVIOUSLY SET BY
 RICH. W. MOSES - NOTES - SHOW - A
 STONE - MARK - FOUND - MON.
 SET - IN - E OF NTS, E + W - REEDS.


- Stone at intersection of N. S. E. W. Pos
- 176.1' S.W. of S.W. Cor. of E. W. Wilson Res.
- 49.4' S.W. of X SPKS in Power Line
- 58.8' W.S.W. of X SPKS in 20" Maple
- 47.5' N.W. of X SPKS in Cor Post, Fc. E. S.
- 56.4' N.E. of Geodetic Mon. # 6 D6
- 47.9' N.E. of X SPKS in Cor Post Fc. S.W.
- 47.0' S.E. of X SPKS in Cor Post.
- 66.0' R.O.W. in Road N + S.
- 66.0' R.O.W. in Road E + W.

MONUMENT - BURIED - 12" Deep

18 17

19 20

STAMPED -




11
 1/4 CORNER SEC 20 - T18N R-4W
 MON. PREVIOUSLY SET BY AT
 RIVEN MEASURES - NOTES - SHOW
 H-STONE - W 25 - FOUND - MON
 SET IN E & F + W ROAD - IN
 LINE - WITH NYS FENCES

- 635.8' E.S.E. CROSS in Culvert Wing N. Side of Rd.
- 340' S of X SPKS. in Cor Post. Fence N.
- 34.8' N. of X SPKS. in Cor Post. Fence S.
- 59.0' N.E. of X SPKS. in 2nd. pole
- 93.7' S.W. of X SPKS in power pole
- 36.4' N.W. of X SPKS in brace post. F. F.
- 68.8' R.O.W. in ROAD E. & W.

MONUMENT - BRICK - 12" DEEP
 STAMPED - 20

X N 7-26-39




W^{1/2} CORNER - R. Sec. - 17 - T78N - R-4W
 Mon. PREVIOUSLY - Set - By - J. J. -
 RYAN - WHOSES - NOTES - SHOW - A
 STONE - WAS - FOUND - Mon. SET
 N. & S. OF - ROAD - IN - LINE -
 WITH - E & W - FENCES.

29.7' E. of X SPKS. in COR. Post. Fence W.
 25.0' W. of X SPKS. in COR. Post. Fence E.
 508.6' N.W. of N.W. COR. of FRANK CHURCHER RES.
 100.0' S.W. of X SPKS. in 30" HACKBERRY
 162.1' N.E. of X SPKS. in telephone pole
 22.2' S.E. of X SPKS. in telephone pole

MONUMENT - BURIED - 12" DEEP

18-17

STAMPED -



NE CORNER - Sec - 18. T 7 N R 4 W
 MON. PREVIOUS 5/4. SET BY ST.
 RYAN. WHOSE NOTES SHOW A
 STONE WAS FOUND MON. SET
 IN $\frac{1}{2}$ OF E & W S. ROADS.

Stone at intersection of N.E. & W.R.
 258.4' N.E. of N.E. Cor. of Fred Barry Res.
 156.9' S.W. of S.W. Cor. of BARN
 41.3' S.E. of X SPKS. in tee pole
 41.7' N.W. of X SPKS. in Cap. Post
 55.0' N.E. of X SPKS. in 13" Walnut
 55.0' R.O.W. in Road South
 67.0' R.O.W. in Road E & W.

MONUMENT BURIED - 12" DEEP

78


1818

STAMPED

X

N 1-26-34
 0


S.F.M.
 78
 1818



N $\frac{1}{4}$ CORNER - SEC - 17 - T. 28 N - R. 4 - W.
 MON. PREVIOUSLY SET BY AT
 RYAN - W. HUS. 55 - NOTES - SHOW - A -
 IRON - PIN - W. 75 - FOUND - MON.
 SET - IN - @ OF E + W - ROAD - IN - LINE
 WITH - S. FENCE

- stone in E. of E + W. Road. Fence S.
- 237.2' S.E. of X SPKS in Cor. Post. Fence N.
- 32.4' N. of X SPKS in Cor. Post. Fence S.
- 32.7' S. of steel fence post
- 136.5' SW. of X SPKS. in telephone pole
- 123.2' N.W. of X SPKS in power pole
- 282.5' N.E. of X SPKS in power pole
- 54.0' S.E. of X SPKS in tel. pole
- 65.0' R.O.W. in Road E + W.

MONUMENT - BORIED - 11" DEEP
 STAMPED 17



SE¹/₄ CORNER - Sec - 34 T78N-R4W
 MONUMENT - PREVIOUSLY - SET -
 BY - [unclear] N - W - HOUSES - NOTES
 SHOW - [unclear] N - W - WAS - FOUND
 MON - SET - IN - S - OF - E - W - ROAD -
 IN - LINE - WITH - N - FENCE

S'

621.7' S. of XSPKS in 30" Elm in N. Percoline
 24.7' S. of XSPKS in Cop. Post. Fence N.
 26.9' N.W. of XSPKS, in Fence post, Fence E+W
 2256.0' S.E. of S.E. Cor. of BARN
 26.9' N.E. of XSPKS in Fence post. Fe. E+W
 25.3' N. of E+W. R.O.W. Fence.
 50.0' R.O.W. in Road E+W.

MONUMENT - BURIED - 12" DEEP
 34


STAMPED -

X

N

7-27-39

34



SE. CORNER. Sec - 33. T78N R4W
 MONUMENT - PREVIOUSLY SET BY
 J. T. HAN - WHOSES NOTES - SHOW
 IT - STONE WAS FOUND - MON. SET
 IN E. OF E + W + N. ROADS. 125.4'
 W. OF MON. NE COR. Sec 4 - T78N -
 R4W.

E.


- 344.2' S.W. of S.W. Cor. of Corn CRIB.
 180.2' S.S.W. of Cross in Culvert W. of E. Side of Road
 48.9' S.E. of X SPKS. in Cor Post Fence N. + W.
 63.0' S.E. of X SPKS. in Electric pole
 42.8' N.E. of X SPKS. in power pole.
 49.9' W.N.W. of X SPKS. in Cor Post Fence
 156.7' W.N.W. of X SPKS. in Cor Post Fence
 157.2' N.W. of X SPKS. in Power Pole
 157.6' W.S.W. of X SPKS. in Power Pole
 337.2' S.W. of X SPKS. in Cor Post Fence
 356.5' S. of E. of FENCE - E.

(1)

MONUMENT - BURIED - 12" DEEP

3334

STAMPED -



W $\frac{1}{4}$ CORNER - Sec-34-T78N-R-4-W
 MONUMENT - PREVIOUSLY - SET - BY
 J. E. PUGH - WHOSE - NOTES - SHOW - A
 STONE - WAS - FOUND - MON. SET - IN
 E. OF S. ROAD - AND - IN - LINE -
 WITH - N + W - FENCE - LINES.


25.3' SSW of X SPKS in 28" Black Locust
 23.0' S of X SPKS in 8" Burr Oak
 33.2' S of steel Cor. Post, Fence N.
 166.9' N.E. of X SPKS in 60" Cottonwood
 33.2' E of X SPKS in Cor. Post, Fence W.
 252.0' N.W. of X SPKS in Cor. Post, Fence E.
 288.2' N. of E. of South Road

MONUMENT - BURIED - 12" Deep

33-34

STAMPED -

N 7-27-39. X
 33-34



NE CORNER Sec-33-T.78N-R-4-W

MONUMENT PREVIOUSLY SET BY

T. J. FLYNN - WHOSES NOTES - SHOW NO

ORIGINAL EVIDENCE FOUND.

MON. SET IN - $\frac{1}{2}$ OF E. W. ROAD

IN-LINE WITH S. FENCE-LINE.

20.8' N. of X SPKS in Car Post Fence S

22.2' S.W. of X SPKS in Fence post N. R.O.W. fc

20.9' S.E. of X SPKS in Fence post N. R.O.W. fc

104.5' S.E. of X SPKS in 20' Fenc

222.6' S.W. of X SPKS in 18' Ash

210.5' N.E. of X SPKS in power pole


124.7' N.W. in fence SPKS in power pole

420' R.O.W. in Post E.W.

MONUMENT BURIED - 12" DEEP

28 27

STAMPED - 33 34



N $\frac{1}{2}$ CORNER - Sec - 34 - T78N - R4W
 MONUMENT - PREVIOUSLY - SET BY
 J. J. PHAN - WHOSES - NOTES - SHOW
 NO - ORIGINAL - EVIDENCE - FOUND.
 MON. SET - IN - E. OF E+W ROAD
 IN - LINE - WITH - N. FENCE LINE.

- 24.7' S. of Fence line, E+W R.O.W. fence
- 25.3' N. of Fence line, E+W R.O.W. fence
- 82.4' S.W. of 2nd pole. (XSPKS.)
- 88.2' W. of 2nd PIPE CULVERT
- 148.8' S.E. of S.E. COR of BARN
- 116.8' S.E. of XSPKS in 28" MAP 20
- 206.8' N.E. of XSPKS in POWER Pole
- 153.5' N.W. of XSPKS in POWER Pole
- 50.0' R.O.W. in ROAD E.S.W.

MONUMENT - BURIED - 12" DEEP


27

STAMPED - 34

X

N. 7-27-39

S. J. M.
H.



NE CORNER - SEC-28-78N-R-4-W
 MONUMENT - PREVIOUSLY SET BY
 J. J. IVAN - NOTES - SHOW
 NO. ORIGINAL EVIDENCE FOUND
 MON. SET IN LINE WITH N-E
 FENCE AND IS 2.0' N. OF S+W
 FENCE LINES


6.2' Wh. P. core in 1 1/2" core
 1.60' S of X SPKS. in Cor. Post Fence 1
 No Other Ties Available

MONUMENT - SURFACE LEVEL

21 24
 28 27

STAMPED -

X




22

N. 1/4 Cor. Sec. 27 - 78-4. W.

At intersection of E. & W. fc. and
fc. N. found cracked limestone
14" x 10" x 4" buried 12" deep on
E. side of cor. post.

55.8' S. of Blazed 24" twin Box Elder
38.2' W. of fc. cor post of fc. S.
78.2' E. of X marks in creased fc. Post.




27
 W 1/4 CORNER - Sec - 22 - T78N - R-40W
 MONUMENT - PREVIOUSLY SET
 BY - J. F. RYAN - WHOSES - NOTES
 SHOW - NO - ORIGINAL - EVIDENCE
 FOUND. MON. SET - IN - LINE -
 WITH - NTS, AND - E. OF W. FENCE
 LINES.

0.4' E. of SPKS in L. of Fence W. 1/2
 66.3' S. of SPKS in END of Fence N. 1/2
 1458.6' S.W. of S.W. COR. of CORN CRIB.
 11.1' N. of SPKS in BRAC. of Fence S. 1/2
 N. Other Test available

MONUMENT - SURFACE - LEVEL
 21 - 22
 STAMPED -

7-28-39 X
 21



NE CORNER - Sec. 21 - T78N - R. 4W
 MONUMENT - PREVIOUS 14 - SET BY
 J. J. RYAN - WHOSES NOTES SHOW
 NO ORIGINAL EVIDENCE FOUND
 MON. SET - IN S. OF E + W. COUNTY
 ROAD "R" OLD IN LINE WITH
 S. FENCE.

- 33.2' S. of North Right of Way fence
- 33.3' N. of x SPKS in Co. Post. Fence S.
- 47.91 NE. of x SPKS in E2. base
- S.E. of x SPKS in power pole
- 70.7' NW. of x SPKS in E2. base
- 111.6' S.W. of x SPKS in power pole
- 261.2' SE 11 " " in power pole
- 65.7' E. of E. of IRON PIPE CORNER
- 66.5' ROW in Co. Road "R"


MONUMENT - BURIED - 12" DEEP

16 15

21 22

STAMPED


16 15
 21 22



N $\frac{1}{2}$ CORNER - Sec - 22 - T18N - R - 4 - W
 MONUMENT - PREVIOUSLY - SET - BY
 JET - RYAN - WHOSES - NOTES - SHOW
 IT - STONE - WAS - FOUND - MON - SET
 IN - LINE - WITH - NTS, E + W,
 FENCE - LINES.

- 3298' E.N.E. of Geodetic Mon. #151
- 17' S.W. of X SPKS. = 11 Cor. Past Fence N.
- 1002.1 W. of X SPKS. in 16" Purple Elm Fence N.
- 310.11' S. of X SPKS. in 8" Elm. & n. Fence N.
- 1317.0 E.S.E. of S.E. COR. of Albert Russ Res.

MONUMENT - SURFACE - LEVEL
 15'
 STAMPED - 22



W $\frac{1}{4}$ CORNER - Sec-15-T78N-R4W

MONUMENT - PREVIOUSLY SET BY

J. J. THOM - WHOSES NOTES SHOW

NO ORIGINAL EVIDENCE FOUND

MON SET IN E+W FENCE LINE

AND W. OF N. FENCE.

3.1' E. of X SPKS in CORNER

10.0' W. of X SPKS in CORNER

431.0' W. of X SPKS in CORNER

No other trees in area

MONUMENT SURFACE - see sketch

X N. 7-28-39



S⁴ CORNER - Sec - 36 - T7S N R - 4 - W

DUG - AND - FOUND - A - BLUE -

FLINT - STONE 13" x 10" x 6"

NO - OTHER - ORIGINAL - EVIDENCE.

LOWERED - SAME - AND - PLACED -

MON. ABOVE MON. SET IN 2 OF

E + W + N. ROADS, IN - LINE - WITH

S. FENCE.

31.3' SSW. OF B. MARK - W. W. HEAD - WALL - CULV.

23.0' SSE. OF B. MARK - IN - E. HEAD - WALL - CULV.

50.2' SE. OF XSPKS - IN - POWER POLE

39.6' N. OF XSPKS - IN - CORNER POST

37.9' NNW. OF XSPKS - IN - FENCE POST

43.5' NNE. OF XSPKS - IN - GATE POST


MONUMENT - BURIED - 12" DEEP

36

STAMPED

See page
30

8-10-39



N.E. cor. Sec. 23-78-4 W.

At intersection of E. & W. fc. & f.c. N
found exposed a Gray Granite
13" X 10" X 8". Hammered same & placed
C.M. above stamped $\frac{14}{13}$ set at surface
level. $\frac{23}{24}$


Corner lines up with E. of road N.

- 7.5' So. East off X.S.P.K. in 8" Catalpa tree
13.9' So. off X.S.P.K. in 10" "
40.9' So/West off X.S.P.K. in 8" "
6.5' East off cor Post

?

12-28-39

P.K.W. - C. of P.



29

W. 1/4 cor. Sec. 38-28-4 W

At intersection of E. & W. fr. and fr. S.
dug hole 3' x 3' x 2' dp. Found Sandstone
27" x 10" x 8" buried 6" dp. on W. side of
cor post. lowered same & placed C.M.
above stamped 25/30 buried 4" dp

10.1' W. of X spks. in Brace post
128.1' E. of Blazed 12" Box Elder

No other ties available

12-11-39

R.K.W. - C. of R.



S. 1/4 cor. Sec. 36-78-AW

In E. & W. top line rd. in line with rd. N.
dug hole 5' x 4' x 3' dp. No evidence found.
Corner restored at proportionate distance
between sec. cors. E. & W. and on true line
between said corners. Set C.M. stamped
buried 12" dp.


36
+

- 22.8' S.S.E. of cross in W. Hd wall conc. culv
26.8' S.W. " " " E. " " "
41.5' S.E. of X SPKS in Pur. pole
41.7' N.N.W. " " " " for cor. post
15.1' W. of N. 1/4 cor. Sec. 1-72-4W

See also
Bk 46 p 12

10-24-40

R.K.W. - C. of P.




N.E. cor. Sec. 25-28-41W

In E of N. & S. rd. (Hwy #76) in line with E of
rd. W. dug hole 5' x 5' x 4' deep. No evidence found.
Corner restored. At this point set S.C.M.
12" deep stamped $\frac{24}{25} \frac{19}{30}$

128.5'	S.S.W. of	X spks. in	Pub. Pole
48.0'	W.S.W. "	" "	Gate post
96.4'	N.W. "	" "	Pub. Pole
58.3'	N.E. "	" "	Tel. "
64.9'	E.S.E. "	" "	Cor. post
34.7'	N.E. "	I.G.S.B.M. #44	

4-11-41
P.K.W. - C. of P.




N.E. Cor. Sec. 14-78-41W

At point indicated by double proportion
 distance between known corners N, E, S. and
 dug hole 6' x 4' x 4' deep. No evidence found.
 Corner restored at this point. Set S.C.M.
 stamped $\frac{11}{13}$ buried 12" deep

210.9' S. of E. of paving
 67.9' S.W. of Xspks. in Pwr. Pole
 113.4' N.N.E. " " " "
 51.6' N.N.W. " " " " Gate post
 13.9' W. of E. R.R. W. of rd.

4-15-41

P.M.W. - C. of P.



N. 1/4 Cor. Sec. 1-78-4-W

In E of E. W. County line road at
point indicated by measure dug hole
10' x 5' x 3' dp. No evidence found. Corner
restored at this point. Set s.c.m.
stamped + 12" below surface of road.
There is no fc. S. of this corner.

216.9' W. of fc. line N.

99.2' W.S.W. of X spk's. 12" 1 1/2" Pine tree.


87.0' N.E. " " " " 8" Bay Elder

11-17-41

R.N.W. - C. of P.

Retred - 5/2/41

36-79-4-W



1-78-4-W


W. 1/4 cor. Sec. 1-29-4W

In N.E. rd in line with f.c.W. dug hole
and came down on top of corrugated culvert
across road. No evidence of corner available.
Drove car cap into culvert for corner. Cap
stamped 241.

34.0'	W. of	X spks. in	col. post
74.6'	N.W.	" "	" Tel. pole
85.0'	N.E.	" "	" Pwr. "
71.6'	S.E.	" "	" Pwr. "
76.9'	S.W.	" "	" Tel. "

11-17-41

R.K.W. - C. of P.




N.E. Cor. Sec 2-78-4W

At intersection of $\frac{1}{2}$ of road south
and the E. & W. Mus-Cadet county
line, dug hole. Point comes adjacent
to the E. rail of the C.R.I. & P.R.R. between
two ties. About 30" deep struck a flat
white limestone, dimensions Not Known.
Restored corner and set C.M. stamped
271 buried 6" deep.

103.4' S. of Milepost 63-10
54.2' S.W. of x spks in Pur. pole
61.8' N.W. of " " " Tel. "
53.1' E.N.E. " " " Pur. "
70.8' E.S.E. " " " Col. post

4-17-41


R.K.W. - C. of P.




In a line between 25 & 26 T78N-R4W. I have checked with our records and have found that at the N.E. corner of Sec. 26 there is a monument where in a survey previous to setting the monument an iron pin was found. The ties to the monument now at this location will be found below.

At the S.W. corner of Sec. 25-78-4W I found that there is a monument set where an original stone had been found and the ties for this monument are found below:

The corner which is still to be set is the $\frac{1}{4}$ corner between Sections 25 & 26.



These ties are found on Page 26 of Book 1.



These ties are found in Book 1 on Page 24.

With these two corners to work from you could proportion your distance for the mile N. & S. and set the $\frac{1}{4}$ corner. It would probably be most logical to start at the S.W. corner of 25 and chain N as there was an original stone found at this point.